

DITCHINGOS THY EMERIES

NOTES:

- 1. SHORING OR TAPERED BANKS WILL BE REQUIRED FOR ANY TRENCH 5' OR MORE IN DEPTH.
- 2. IN ALL CASES A MINIMUM OF 3" OF PAVING OVER 6" CLASS 2 A.B. OR EQUIVALENT IS REQUIRED. PAVING MATERIAL TO BE THE SAME AS THAT REMOVED. (NEW PAVEMENT TO BE 1" THICKER THAN ORIGINAL.)
- 3. DECOMPOSED GRANITE MAY NOT BE USED FOR BACK FILL OR PIPE BEDDING.
- 4. COMPACTION TESTS BY A CERTIFIED LAB WILL BE REQUIRED FOR ALL TRENCH CUTS OR OTHER EXCAVATION. CONTRACTOR TO BEAR FULL EXPENSE OF ALL TESTING.
- 5. UPPER LIFT OF NEW A.C. PAVEMENT SHALL CONTAIN AGGREGATE OF 1/2"
 MAX SIZE.
- 6. A HEATER REMIX PROCESS MAY BE USED IN LIEU OF THE "T" SLOT OVERLAY. THE HEATER REMIX PROCESS CALLS FOR THE EDGES OF THE SAWCUT TRENCH LINE TO BE HEATED TO A POINT THAT ALLOWS THE EXISTING A.C. TO BECOME PLIABLE. THE EXISTING AND NEW A.C. IS THEN SCARIFIED, MIXED TO A HOMOGENEOUS MIXTURE AND THEN COMPACTED TO PROVIDE A SEAMLESS JOINT ALONG THE TRENCH EDGES. A REJUVENATING AGENT MAY BE REQUIRED TO RESTORE THE BINDER IN THE EXISTING A.C.
- 7. ALL TRENCH PATCHES ARE TO BE SEALED (FOG SEALED) AS PER CALTRANS STD. SECTION 37 AND 94/TABLE #1 SS1 OR SS1H